EXISTING PANELBOARD WDP SCHEDULE

SEE POWER RISER DIAGRAM FOR RATINGS

LOAD SERVED	LOAD (AMPS) A	B	C	BKR TRIP	CKT NO.	PHASE A B C	CKT NO.	BKR TRIP	LOAD (AMPS) A	B	C	LOAD SERVED
EXISTING CONDENSOR				100/3P	1		2	125/3P				EXISTING COMPUTER LAB XFMR
							4					
EXISTING CONDENSOR AHU #4				125/3P	7		8	20/1P				SPARE
							10	20/1P				SPARE
							12	20/1P				SPARE
SPARE				20/1P	13		14	20/1P				SPARE
SPARE				20/1P	15		16	20/1P				SPARE
SPARE				20/1P	17		18	20/1P				SPARE
SPARE				20/1P	19		20	20/1P				SPARE
SPARE				20/1P	21		22	20/1P				SPARE
SPARE				20/1P	23		24	20/1P				SPARE
SPARE				20/1P	25		26	100/3P	5.2			PANEL PG
SPARE				20/1P	27					11.2		
SPARE				20/1P	29						13.5	

NOTES:
1. PANEL IS MANUFACTURED BY SIEMENS, TYPE S3
2. BOLD TEXT INDICATES NEW LOAD AND BREAKER.

PANELBOARD PG SCHEDULE

SEE POWER RISER DIAGRAM FOR RATINGS

LOAD SERVED	LOAD (AMPS) A	B	C	BKR TRIP	CKT NO.	PHASE A B C	CKT NO.	BKR TRIP	LOAD (AMPS) A	B	C	LOAD SERVED
LIGHTING	5.2			20/1P	1		2	20/1P				SPARE
LIGHTING		11.2		20/1P	3		4	20/1P				SPARE
LIGHTING			13.5	20/1P	5		6	20/1P				SPARE
SPARE				20/1P	7		8	20/1P				SPARE
SPARE				20/1P	9		10	20/1P				SPARE
SPARE				20/1P	11		12	20/1P				SPARE
SPARE				20/1P	13		14	20/1P				SPARE
SPARE				20/1P	15		16	20/1P				SPARE
SPARE				20/1P	17		18	20/1P				SPARE
SPARE				20/1P	19		20	20/1P				SPARE
SPARE				20/1P	21		22	20/1P				SPARE
SPARE				20/1P	23		24	20/1P				SPARE
SPARE				20/1P	25		26	20/1P				SPARE
SPARE				20/1P	27		28	20/1P				SPARE
SPARE				20/1P	29		30	20/1P				SPARE
SPARE				20/1P	31		32	20/1P				SPARE
SPARE				20/1P	33		34	20/1P				SPARE
SPARE				20/1P	35		36	20/1P				SPARE
SPARE				20/1P	37		38	20/1P				SPARE
SPARE				20/1P	39		40	20/1P				SPARE
SPARE				20/1P	41		42	20/1P				SPARE
TOTAL	5.2	11.2	13.5						0.0	0.0	0.0	TOTAL

TOTAL CONNECTED AMPS A: 5.2 B: 11.2 C: 13.5

NOTES:
1. THIS PANEL IS NEW AND IS PROVIDED TO REPLACE EXISTING PANEL OF THE SAME NAME AT A NEW LOCATION. COORDINATE LOCATION ON PLANS. ANY BREAKERS MADE AVAILABLE VIA DEMOLITION SHALL LABELED AS SPARE.

PANELBOARD LG SCHEDULE

SEE POWER RISER DIAGRAM FOR RATINGS

LOAD SERVED	LOAD (AMPS) A	B	C	BKR TRIP	CKT NO.	PHASE A B C	CKT NO.	BKR TRIP	LOAD (AMPS) A	B	C	LOAD SERVED
RECEPTACLES	6.0			20/1P	1		2	20/1P	10.5			RECEPTACLES
RECEPTACLES		9.0		20/1P	3		4	20/1P		12.0		RECEPTACLES
RECEPTACLE – FAX			10.0	20/1P	5		6	20/1P			6.0	PRINTER/FAX
RECEPTACLES	4.5			20/1P	7		8	20/1P	10.5			RECEPTACLES
COPIER		10.0		20/1P	9		10	20/1P		8.0		COPIER
RECEPTACLES			6.0	20/1P	11		12	20/1P			9.0	RECEPTACLES
RECEPTACLES	6.0			20/1P	13		14	20/1P	10.5			RECEPTACLES
RECEPTACLES		9.0		20/1P	15		16	20/1P		10.5		RECEPTACLES
RECEPTACLE – EWC			8.0	20/1P	17		18	20/1P			10.5	RECEPTACLES
RECEPTACLES	9.0			20/1P	19		20	20/1P				SPARE
RECEPTACLES		10.5		20/1P	21		22	20/1P				SPARE
RECEPTACLES			12.0	20/1P	23		24	20/1P			3.0	RECEPTACLES
RECEPTACLES	12.0			20/1P	25		26	20/1P				SPARE
RECEPTACLES		13.5		20/1P	27		28	20/1P				SPARE
⚠2 TRACK LTG FIXTURES			6.2	20/1P	29		30	20/1P				SPARE
TRACK LTG FIXTURES	5.0			20/1P	31		32	20/1P				SPARE
SPARE				20/1P	33		34	20/1P				SPARE
SPARE				20/1P	35		36	20/1P				SPARE
SPARE				20/1P	37		38	100/3P	7.5			PANEL LH
WATER HEATER, WH-2 4.5 KW		22.0		30/2P	39					23.9		
			22.0								14.4	
TOTAL	42.5	74.0	64.2						39.0	54.4	42.9	TOTAL

TOTAL CONNECTED AMPS A: 81.5 B: 128.4 C: 107.1

NOTES:
1. THIS PANEL IS NEW AND IS PROVIDED TO REPLACE EXISTING PANEL OF THE SAME NAME AT A NEW LOCATION. COORDINATE LOCATION ON PLANS. ANY BREAKERS MADE AVAILABLE VIA DEMOLITION SHALL LABELED AS SPARE.

PANELBOARD LH SCHEDULE

SEE POWER RISER DIAGRAM FOR RATINGS

LOAD SERVED	LOAD (AMPS) A	B	C	BKR TRIP	CKT NO.	PHASE A B C	CKT NO.	BKR TRIP	LOAD (AMPS) A	B	C	LOAD SERVED
ROOF RECEPTACLES	4.5			20/1P	1		2	20/1P	3.0			EXHAUST FAN, EF-9
HVAC TERMINAL BOX		8.0		20/1P	3		4	20/1P		1.5		EXHAUST FAN, EF-10
SPARE				20/1P	5		6	20/1P				SPARE
SPARE				20/1P	7		8	20/1P				SPARE
SPARE				20/1P	9		10	20/1P				SPARE
SPARE				20/1P	11		12	20/1P				SPARE
SPARE				20/1P	13		14	20/1P				SPARE
SPARE				20/1P	15		16	20/1P				SPARE
SPARE				20/1P	17		18	20/1P				SPARE
SPARE				20/1P	19		20	20/1P				SPARE
SPARE				20/1P	21		22	20/1P				SPARE
SPARE				20/1P	23		24	20/1P				SPARE
SPARE				20/1P	25		26	20/1P				SPARE
ELECTRIC UNIT HTR. EUH-1		7.2		20/2P	27		28	20/2P		7.2		ELECTRIC UNIT HTR. EUH-2
			7.2								7.2	
TOTAL	4.5	15.2	7.2						3.0	8.7	7.2	TOTAL

TOTAL CONNECTED AMPS A: 7.5 B: 23.9 C: 14.4

PANELBOARD LF SCHEDULE

SEE POWER RISER DIAGRAM FOR RATINGS

LOAD SERVED	LOAD (AMPS) A	B	C	BKR TRIP	CKT NO.	PHASE A B C	CKT NO.	BKR TRIP	LOAD (AMPS) A	B	C	LOAD SERVED
RECEPTACLES	10.5			20/1P	1		2	20/1P	6.0			RECEPTACLES
RECEPTACLES		10.0		20/1P	3		4	20/1P		12.5		INST. WATER HTR
REFRIGERATOR			10.5	20/1P	5		6	20/1P			6.0	EWC
RECEPTACLES	7.5			20/1P	7		8	20/1P	12.0			VENDING MACHINES
RECEPTACLES		9.0		20/1P	9		10	20/1P		12.0		VENDING MACHINES
RECEPTACLES			6.0	20/1P	11		12	20/1P			12.0	VENDING MACHINES
RECEPTACLES	12.0			20/1P	13		14	20/1P	12.0			VENDING MACHINES
SPARE				20/1P	15		16	20/1P		6.0		RECEPTACLES
RECEPTACLES			4.5	20/1P	17		18	20/1P			2.0	LED LIGHTING
RECEPTACLES	4.5			20/1P	19		20	20/1P				SPARE
RECEPTACLES		12.0		20/1P	21		22	20/1P				SPARE
RECEPTACLES			9.0	20/1P	23		24	20/1P				SPARE
RECEPTACLES	12.0			20/1P	25		26	20/1P				SPARE
RECEPTACLES		7.5		20/1P	27		28	20/1P				SPARE
RECEPTACLES			9.0	20/1P	29		30	20/1P				SPARE
RECEPTACLES	12.0			20/1P	31		32	20/1P				SPARE
RECEPTACLES		13.5		20/1P	33		34	20/1P				SPARE
RECEPTACLES			10.5	20/1P	35		36	20/1P				SPARE
RECEPTACLES	13.5			20/1P	37		38	35/1P	6.0			HVAC TERM BOXES
SPARE				20/1P	39		40	20/2P		7.2		ELECTRIC UNIT HTR.
SPARE				20/1P	41						7.2	EUH-8
TOTAL	72.0	52.0	49.5						36.0	37.7	27.2	TOTAL

TOTAL CONNECTED AMPS A: 108.0 B: 89.7 C: 76.7

ELECTRICAL LOAD SUMMARY

LOAD DESCRIPTION	CONNECTED LOAD	DEMAND FACTOR	DEMAND LOAD
LIGHTING	155.2 KVA	100%	155.2 KVA
RECEPTACLES	109.1 KVA	NOTE – 1	59.6 KVA
AIR CONDITIONING	157.7 KVA	80%	126.1 KVA
HEATING	14.7 KVA	0%	0.0 KVA
HEAT PUMP	0.0 KVA	80%	0.0 KVA
VENTILATION	5.1 KVA	100%	5.1 KVA
MISCELLANEOUS	68.8 KVA	60%	41.3 KVA
WATER HEATER	22.6 KVA	70%	15.8 KVA
TOTAL	533.2 KVA		403.1 KVA

NOTES:
1. 1st 10 KVA @ 100%, REMAINDER @ 50%
2. THE EXISTING 1000KVA SERVICE TRANSFORMER FAULT CURRENT IS 37,517 SYM. AMPRES @ THE SECONDARY BUSHINGS.
3. DVP'S PEAK DEMAND FOR THE PAST 24 MONTHS IS 261 KW

PANELBOARD PC SCHEDULE

SEE POWER RISER DIAGRAM FOR RATINGS

LOAD SERVED	LOAD (AMPS) A	B	C	BKR TRIP	CKT NO.	PHASE A B C	CKT NO.	BKR TRIP	LOAD (AMPS) A	B	C	LOAD SERVED
SPARE				20/1P	1		2	20/1P	1.3			LIGHTING
SPARE				20/1P	3		4	20/1P		8.0		LIGHTING
SPARE				20/1P	5		6	20/1P			8.7	LIGHTING
SPARE				20/1P	7		8	20/1P	6.3			LIGHTING
LIGHTING		9.7		20/1P	9		10	20/1P		11.1		LIGHTING
LIGHTING			8.3	20/1P	11		12	20/1P				SPARE
SPARE				20/1P	13		14	20/1P				SPARE
SPARE				20/1P	15		16	20/1P				SPARE
SPARE				20/1P	17		18	20/1P				SPARE
SPARE				20/1P	19		20	20/1P				SPARE
SPARE				20/1P	21		22	20/1P				SPARE
SPARE				20/1P	23		24	20/1P				SPARE
SPARE				20/1P	25		26	20/1P				SPARE
SPARE				20/1P	27		28	20/1P				SPARE
SPARE				20/1P	29		30	20/1P				SPARE

NOTES:
1. THIS PANEL IS NEW AND IS PROVIDED TO REPLACE EXISTING PANEL OF THE SAME NAME AT THE SAME LOCATION. ANY BREAKERS MADE AVAILABLE VIA DEMOLITION SHALL LABELED AS SPARE.

PANELBOARD CDP SCHEDULE

SEE POWER RISER DIAGRAM FOR RATINGS

LOAD SERVED	LOAD (AMPS) A	B	C	BKR TRIP	CKT NO.	PHASE A B C	CKT NO.	BKR TRIP	LOAD (AMPS) A	B	C	LOAD SERVED
PANEL WC7	33.0			100/3P	1		2	150/3P	28.5			PANEL LIT
		30.0								33.0		
			27.0								30.0	
SPARE				20/1P	7		8	20/1P				SPARE
SPARE				20/1P	9		10	20/1P				SPARE
SPARE				20/1P	11		12	20/1P				SPARE
SPARE				20/1P	13		14	20/1P				SPARE
SPARE				20/1P	15		16	20/1P				SPARE
SPARE				20/1P	17		18	20/1P				SPARE
SPARE				20/1P	19		20	20/1P				SPARE
SPARE				20/1P	21		22	20/1P				SPARE
SPARE				20/1P	23		24	20/1P				SPARE
SPARE				20/1P	25		26	20/1P				SPARE
SPARE				20/1P	27		28	20/1P				SPARE
SPARE				20/1P	29		30	20/1P				SPARE
TOTAL	33.0	30.0	27.0						28.5	33.0	30.0	TOTAL

TOTAL CONNECTED AMPS A: 61.5 B: 63.0 C: 57.0

NOTES:
1. PROVIDED PANEL WITH ISOLATED GROUND BUS.

PANELBOARD LIT SCHEDULE

SEE POWER RISER DIAGRAM FOR RATINGS

LOAD SERVED	LOAD (AMPS) A	B	C	BKR TRIP	CKT NO.	PHASE A B C	CKT NO.	BKR TRIP	LOAD (AMPS) A	B	C	LOAD SERVED
RECEPTACLES	12.0			20/1P	1		2	20/1P	12.0			RECEPTACLES
RECEPTACLES		12.0		20/1P	3		4	20/1P		12.0		RECEPTACLES
RECEPTACLES			12.0	20/1P	5		6	20/1P			12.0	RECEPTACLES
SPARE				20/1P	7		8	20/1P	4.5			RECEPTACLES
SPARE				20/1P	9		10	20/1P		9.0		RECEPTACLES
SPARE				20/1P	11		12	20/1P			6.0	RECEPTACLES
SPARE				20/1P	13		14	20/1P				SPARE
SPARE				20/1P	15		16	20/1P				SPARE
SPARE				20/1P	17		18	20/1P				SPARE
SPARE				20/1P	19		20	20/1P				SPARE
SPARE				20/1P	21		22	20/1P				SPARE
SPARE				20/1P	23		24	20/1P				SPARE
SPARE				20/1P	25		26	20/1P				SPARE
SPARE				20/1P	27		28	20/1P				SPARE
SPARE				20/1P	29		30	20/1P				SPARE
SPARE				20/1P	31		32	20/1P				SPARE
SPARE				20/1P	33		34	20/1P				SPARE
SPARE				20/1P	35		36	20/1P				SPARE
SPARE				20/1P	37		38	20/1P				SPARE
SPARE				20/1P	39		40	20/1P				SPARE
SPARE				20/1P	41		42	20/1P				SPARE
TOTAL	12.0	12.0	12.0						16.5	21.0	18.0	TOTAL

TOTAL CONNECTED AMPS A: 28.5 B: 33.0 C: 30.0

NOTES:
1. PROVIDED PANEL WITH ISOLATED GROUND BUS.

PANELBOARD LDP SCHEDULE

SEE POWER RISER DIAGRAM FOR RATINGS

LOAD SERVED	LOAD (AMPS) A	B	C	BKR TRIP	CKT NO.	PHASE A B C	CKT NO.	BKR TRIP	LOAD (AMPS) A	B	C	LOAD SERVED
PANEL LC	229.7			400/3P	1		2	225/3P	76.5			PANEL LG
		219.1								128.4		
			249.7								108.9	
FACP	8.0			20/1P	7		8	20/1P	1.5			RECEPTACLE
ELEC. UNIT HTR, UH-9		9.0		20/2P	9		10	20/2P		9.0		ELEC. UNIT HTR, UH-10
			9.0								9.0	
EHAUST FAN, EF-11	3.0			15/1P	13		14	20/3P	6.6			JOCKEY PUMP, 1 1/2 HP
EHAUST FAN, EF-12		2.0		15/1P	15					6.6		
SPARE				20/1P	17						6.6	
SPARE				20/1P	19		20	20/1P				SPARE
SPARE				20/1P	21		22	20/1P				SPARE
SPARE				20/1P	23		24	20/1P				SPARE
PANEL LB NOTE-1	0.0			225/3P	25		26	225/3P	108.0			PANEL LF
		0.0								89.7		
			0.0								76.7	
SPACE ONLY				20/1P	31		32	20/1P				SPACE ONLY
SPACE ONLY				20/1P	33		34	20/1P				SPACE ONLY
SPACE ONLY				20/1P	35		36	20/1P				SPACE ONLY
SPACE ONLY				20/1P	37		38	20/1P				SPACE ONLY
SPACE ONLY				20/1P	39		40	20/1P				SPACE ONLY
SPACE ONLY				20/1P	41		42	20/1P				SPACE ONLY
TOTAL	240.7	230.1	258.7						192.6	233.7	201.2	TOTAL

TOTAL CONNECTED AMPS A: 433.3 B: 463.8 C: 459.9

NOTES:
1. THIS PANEL IS A "RELOCATED" NEW PANEL WITH EXISTING (UNDETERMINED) LOADS.

SWITCHBOARD MSB SCHEDULE

HORIZONTAL BUS: 1600A VERTICAL BUS: TAPERED AS REQUIRED 100%
VOLTAGE: 480Y/277 VOLT, 3 PHASE, 4 WIRE BRACING: 42 KAIC 100% COPPER

SECTION	DESCRIPTION
I	DOMINION VIRGINIA POWER COMPLIANT UTILITY SECTION
II	1600A MAIN CIRCUIT BREAKER (100% RATED) AND METERING
III	EMPTY CABLE PULL SECTION
	DISTRIBUTION

	COMP. NO.	LOAD SERVED	LOAD (AMPS) A	B	C	DISCONNECT DEVICE POLES	TYPE	FRAME	TRIP	NOTES
IV	1	EXISTING CHILLER				3	CB	400	400	NOTE–1
	3	EXISTING PANEL NPD				3	CB	100	100	NOTE–1
	5	EXISTING PANEL NPE				3	CB	225	225	NOTE–1
	7	EXISTING PANEL PB				3	CB	225	225	NOTE–1
	9	EXISTING BOILER #1				3	CB	400	400	NOTE–1
	2	EXISTING PANEL WDP				3	CB	400	400	NOTE–1
	4	EXISTING BOILER #2				3	CB	400	400	NOTE–1
	6	PANEL LA (VIA EXIST XFMR)				3	CB	225	150	NOTE–1
	8	TVSS				3	CB	100	60	
	10	SPACE ONLY								
V	1	PANEL PC	19.6	28.8	17.0	3	CB	225	225	
	3	PANEL MP	214.0	214.0	214.0	3	CB	400	400	
	5	PANEL PA	99.0	99.0	99.0	3	CB	225	225	
	7	TVSS					CB	100	60	
	2	PANEL CDP VIA X'FMR	26.7	27.3	24.7	3	CB	225	150	
	4	PANEL LDP VIA X'FMR	187.8	201.0	199.3	3	CB	400	400	
	6	SPACE ONLY								
	8	SPACE ONLY								

NOTES:
1. EXISTING LOADS ARE UNKNOWN. BREAKER SIZES ARE DETERMINED FROM EQUIPMENT SERVED.
2. SWITCHBOARD SIZE IS BASED ON DOMINION VIRGINIA POWER'S PEAK DEMAND LOAD WITH THE ADDITION OF NEW PANEL LOADS,

PANELBOARD MP SCHEDULE

SEE POWER RISER DIAGRAM FOR RATINGS

LOAD SERVED	LOAD (AMPS) A	B	C	BKR TRIP	CKT NO.	PHASE A B C	CKT NO.	BKR TRIP	LOAD (AMPS) A	B	C	LOAD SERVED
OUTSIDE NIGHT LIGHTS	22.0			30/3P	1		2	15/3P	7.0			CONDENSER #1
		22.0								7.0		
			22.0								7.0	
DUAL TEMP PUMP RECIRC PUMP #1	12.0			20/3P	3		4	70/3P	54.0			XFMR THIS ROOM
		12.0								54.0		
			12.0								54.0	
CHILLER PUMP RECIRC PUMP #2	22.0			30/3P	5		6	15/3P	7.0			CONDESNOR #2
		22.0								7.0		
			22.0								7.0	
OUTSIDE LTS	30.0			40/3P	7		8	20/1P				SPARE
		30.0					10	20/1P				SPARE
			30.0				12	20/1P				SPARE
FUTURE PNL RM 108	60.0			100/3P	9		14	20/1P				SPARE
		60.0					16	20/1P				SPARE
			60.0				18	20/1P				SPARE
SPARE				20/1P	11		20	20/1P				SPARE
SPARE				20/1P	13		22	20/1P				SPARE
SPARE				20/1P	15		24	20/1P				SPARE
SPARE				20/1P	17		26	20/1P				SPARE
SPARE				20/1P	19		28	20/1P				SPARE
SPARE				20/1P	21		30	20/1P				SPARE

NOTES:
1. THIS PANEL IS NEW AND IS PROVIDED TO REPLACE EXISTING PANEL OF THE SAME NAME AT SAME LOCATION. ANY BREAKERS MADE AVAILABLE VIA DEMOLITION SHALL LABELED AS SPARE.

PANELBOARD PA SCHEDULE

SEE POWER RISER DIAGRAM FOR RATINGS

LOAD SERVED	LOAD (AMPS) A	B	C	BKR TRIP	CKT NO.	PHASE A B C	CKT NO.	BKR TRIP	LOAD (AMPS) A	B	C	LOAD SERVED
EXISTING LOADS				20/1P	1		2	20/1P				EXISTING LOADS
EXISTING LOADS				20/1P	3		4	20/1P				EXISTING LOADS
EXISTING LOADS				20/1P	5		6	20/1P				EXISTING LOADS
EXISTING LOADS				20/1P	7		8	20/1P				EXISTING LOADS
EXISTING LOADS				20/1P	9		10	20/1P				EXISTING LOADS
EXISTING LOADS				20/1P	11		12	20/1P				EXISTING LOADS
EXISTING LOADS				20/1P	13		14	20/1P				EXISTING LOADS
EXISTING LOADS				20/1P	15		16	20/1P				EXISTING LOADS
EXISTING LOADS				20/1P	17		18	20/1P				EXISTING LOADS
EXISTING LOADS				20/1P	19		20	20/1P				EXISTING LOADS
EXISTING LOADS				20/1P	21		22	20/1P				EXISTING LOADS
EXISTING LOADS				20/1P	23		24	20/1P				EXISTING LOADS
EXIST. WATER HEATER	22.0			30/3P	25		26	40/3P	32.0			EXIST. WATER HEATER BOILER RM
		22.0								32.0		
			22.0								32.0	
EXISTING BOILER PUMP	7.0			15/3P	31		32	15/3P	8.0			EXIST AIR COMPR. LAB AREA
		7.0								8.0		
			7.0								8.0	
EXISTING AIR COMPRESSOR	22.0			30/3P	37		38	15/3P	8.0			EXIST AIR HANDLING UNIT #3
		22.0								8.0		
			22.0								8.0	

NOTES:
1. THIS PANEL IS NEW AND IS PROVIDED TO REPLACE EXISTING PANEL OF THE SAME NAME AT SAME LOCATION. ANY BREAKERS MADE AVAILABLE VIA DEMOLITION SHALL LABELED AS SPARE.

PANELBOARD PB SCHEDULE

SEE POWER RISER DIAGRAM FOR RATINGS

LOAD SERVED	LOAD (AMPS) A	B	C	BKR TRIP	CKT NO.	PHASE A B C	CKT NO.	BKR TRIP	LOAD (AMPS) A	B	C	LOAD SERVED
EXISTING LIGHTING				20/1P	1		2	20/1P				EXISTING LIGHTING
EXISTING LIGHTING				20/1P	3		4	30/1P				EXISTING DUCT HTR
EXISTING LIGHTING				20/1P	5		6	30/1P				EXISTING DUCT HTR
EXIST ROOF TOP UNIT RTU-2	11.0			20/3P	7		8	20/3P	11.0			EXISTING HVAC UNIT RTU-3
		11.0								11.0		
			11.0								11.0	
EXISTING HVAC UNIT ACCU-3	38.0			50/3P	13		14	20/3P	12.4			EXISTING HVAC UNIT RTU-4
		38.0								12.4		
			38.0								12.4	
EXISTING HVAC UNIT ACCU-2	48.0			70/3P	19		20	35/3P	25.2			EXISTING HVAC UNIT ACCU-4
		48.0								25.2		
			48.0								25.2	
LIGHTING				20/1P	21		26	20/1P				SPARE
LIGHTING				20/1P	23		28	20/1P				SPARE
LIGHTING				20/1P	25		30	20/1P				SPARE
LIGHTING				20/1P	31		32	20/1P				SPARE
SPARE				20/1P	33		34	20/1P				SPARE
SPARE				20/1P	35		36	20/1P				SPARE
SPARE				20/1P	37		38	20/1P				SPARE
SPARE				20/1P	39		40	20/1P				SPARE
SPARE				20/1P	41		42	20/1P				SPARE

NOTES:
1. THIS PANEL IS NEW AND IS PROVIDED TO REPLACE EXISTING PANEL OF THE SAME NAME AT A NEW LOCATION. COORDINATE LOCATION ON PLANS. ANY BREAKERS MADE AVAILABLE VIA DEMOLITION SHALL LABELED AS SPARE.

nbj ARCHITECTURE
A Professional Limited Company
GROVE PARK SQUARE
11537-B NUCKOLS ROAD
Richmond, Virginia 23059
℡ (804) 273-9811 fax: (804) 273-9843

RAPPAHANNOCK COMMUNITY COLLEGE
CAMPUS RENOVATIONS
WARSAW + GLENNS, VIRGINIA
PC: 260-17712

WARSAW CAMPUS ELECTRICAL PANELBOARD SCHEDULES

Date: MARCH 3, 2010

REVISIONS

NO.	DATE
⚠2	MARCH 3, 2010

COMMONWEALTH OF VIRGINIA
JAMES S. BEDOIS
Lic. No. 032929
PROFESSIONAL ENGINEER
3.3.10

Sheet
E6.1W
File Number

PAGE COLLABORATIVE
MECHANICAL ELECTRICAL ENGINEERS
VIRGINIA BEACH, VA · 757-499-7229